

## **Abstract**

An internal lintel where masonry units are mechanically attached to a suspension member 3 by means of an anchor 2. The suspension member is attached to a hidden support beam 6 by means of a continuous strut 5 and strut fastener 8. No part of the lintel is visible after construction of the wall is complete.